

**Date:** 5/11/2016 **Author:** CentraCom **Project:** Mosiac Network  
**Comments:**  
Installing (2) 1 1/4" conduits/fiber.  
Directional drill road bore.

Taper, Buffer Zone & Sign Spacing				
Posted speed	Mini Taper Length	Length of Buffer	Min Sign Spacing	Devices Spacing
30	180'	200'	100'	15'
35	245'	250'	350'	20'
40	320'	305'	350'	27'
45	540'	380'	500'	45'
50	600'	425'	500'	50'
55	660'	495'	500'	55'
60	720'	570'	500'	60'
65	780'	645'	500'	65'



Directional bore road crossing

Installing (2) 1 1/4" conduits/fiber.  
Directional drill 3' behind existing sidewalk.

SHOULDER WORK  
UTILITY WORK AHEAD  
ROAD WORK AHEAD