

**Date:** 7/21/2016 **Author:** CentraCom **Project:** Syringa Sprint Tower

**Comments:**  
Installing 1 1/4" conduit/fiber

Taper, Buffer Zone & Sign Spacing					
Posted speed	Mini Taper Length	Length of Buffer	Min Sign Spacing	Devices Spacing	
30	180'	200'	100'	15'	
35	245'	250'	350'	20'	
40	320'	305'	350'	27'	
45	540'	380'	500'	45'	
50	600'	425'	500'	50'	
55	660'	495'	500'	55'	
60	720'	570'	500'	60'	
65	780'	645'	500'	65'	

UTILITY WORK AHEAD  
SHOULDER WORK  
ROAD WORK AHEAD

Installing conduit/fiber

