

Date: 3/9/2017 **Author:** CentraCom **Project:** Salem City Offices SR 198

Comments:

Installing aerial fiber Hwy 198 crossing.
MPM 8.5

Taper, Buffer Zone & Sign Spacing				
Posted speed	Mini Taper Length	Length of Buffer	Min Sign Spacing	Devices Spacing
30	180'	200'	100'	15'
35	245'	250'	350'	20'
40	320'	305'	350'	27'
45	540'	380'	500'	45'
50	600'	425'	500'	50'
55	660'	495'	500'	55'
60	720'	570'	500'	60'
65	780'	645'	500'	65'

Safety zone

Attach aerial fiber to existing poles

Safety zone

