

Date: 4/17/2017 Author: CentraCom Project: Central Valley Medical 1500 N Nephi

Comments:
Installing 1 1/4" conduit/fiber to temporary trailers.

Taper, Buffer Zone & Sign Spacing				
Posted speed	Mini Taper Length	Length of Buffer	Min Sign Spacing	Devices Spacing
30	180'	200'	100'	15'
35	245'	250'	350'	20'
40	320'	305'	350'	27'
45	540'	380'	500'	45'
50	600'	425'	500'	50'
55	660'	495'	500'	55'
60	720'	570'	500'	60'
65	780'	645'	500'	65'



Installing 1 1/4" conduit/fiber

Accessing existing handhole

Road bore directional drill
Installing conduit/fiber

ROAD WORK AHEAD
LEFT SHOULDER WORK AHEAD
SHOULDER WORK

ROAD WORK AHEAD
LEFT SHOULDER WORK AHEAD
SHOULDER WORK

SHOULDER WORK
ROAD WORK AHEAD