



Accessing existing UDOT handhole

Date: 5/17/2017 Author: CentraCom Project: CMS University Parkway Orem

Comments:

Accessing existing UDOT handholes.

Taper, Buffer Zone & Sign Spacing				
Posted speed	Mini Taper Length	Length of Buffer	Min Sign Spacing	Devices Spacing
30	100'	200'	100'	15'
35	245'	250'	350'	20'
40	320'	305'	350'	27'
45	540'	380'	500'	45'
50	600'	425'	500'	50'
55	660'	495'	500'	55'
60	720'	570'	500'	60'
65	780'	645'	500'	65'

SHOULDER WORK
UTILITY WORK AHEAD
ROAD WORK AHEAD