

Date: 5/17/2017 Author: CentraCom Project: CMS University Parkway Orem

Comments:

Accessing existing handhole. Installing handhole next to existing UDOT handhole.

Taper, Buffer Zone & Sign Spacing					
Posted speed	Mini Taper Length	Length of Buffer	Min Sign Spacing	Devices Spacing	
30	180'	200'	100'	15'	
35	245'	250'	350'	20'	
40	320'	305'	350'	27'	
45	540'	380'	500'	45'	
50	600'	425'	500'	50'	
55	660'	495'	500'	55'	
60	720'	570'	500'	60'	
65	780'	645'	500'	65'	



ROAD WORK AHEAD

SHOULDER WORK

Accessing existing UDOT handhole.

SHOULDER WORK

ROAD WORK AHEAD

SHOULDER WORK

UTILITY WORK AHEAD

ROAD WORK AHEAD

ROAD WORK AHEAD

ROAD WORK AHEAD

ROAD WORK AHEAD

SHOULDER WORK

UTILITY WORK AHEAD

ROAD WORK AHEAD

Installing CentraCom handhole next to existing UDOT handhole.