



Installing 1 1/4" conduit/fiber

Accessing existing handhole

Date: 6/23/2017 **Author:** CentraCom **Project:** Summit Academy Bluffdale

Comments:

Installing 1/4" conduit/fiber.
Accessing existing handhole.

Posted speed	Taper, Buffer Zone & Sign Spacing			
	Mini Taper Length	Length of Buffer	Min Sign Spacing	Devices Spacing
30	180'	200'	100'	15'
35	245'	250'	350'	20'
40	320'	305'	350'	27'
45	540'	300'	500'	45'
50	600'	425'	500'	50'
55	660'	485'	500'	55'
60	720'	570'	500'	60'
65	780'	645'	500'	65'